	Items of work	Quantity	Per	Rate Rs.	a.	p.	Remarks
9.	Teakwood wrought and put up ...	748·01	C.ft.				
10.	Teakwood ornamental eaves board 9″ x 1″ ...	724	R.ft.				
11.	Roofing with Mangalore pattern first class Yelahanka tiles on teak reepers, etc., complete	114·78	Sqr.				
12.	Do Ridge tiles set in mortar ...	313	R.ft.				
13.	Zinc sheet for valleys 1½′ wide with teakwood planks below, complete	75	,,				
14.	Pucca terrace roofiing	324	Sqr.				
15.	British standard or Tata Steel girders and joists with one coat of antierosive paint and hoisting and fixing, complete ...	12	Cwts.				
16.	Teak arched terrace with kappi in chunam and two courses of flat tiles, etc., complete ...	3·25	Sqr.				
17.	Chunam mortar plastering ...	266·16	,,				
18.	Flooring with Kadappa slabs on 3″ concrete bed and cement pointing, complete ...	67·02	,,				
19.	Silicate painting two coats to doors and windows	82·45	,,				
20.	Wood oiling 2 coats for wood work ..	115 01	,,				
21.	Dwarf parapet wall as per design	64	R.ft.				
22.	Light cornice work do	65	,,				
23.	Chimney for smoke escape	L. S.	..				
24.	Chunam borders	130	,,				
24 (*a*)	White and colour washing 2 coats ...	266·00	Sqr.				
25.	Wire cut brick wall with ex-metal for every 3rd course and plastering, complete ...	132	S. ft.				

V. V. KARVE,
Executive Engineer.

KADUR DIVISION.

Abstract Notification dated 17th *November* 1928.

Attention of the Public is invited to the notification calling for tenders for Restoring Hariharpur Mutt building, published on pages 1387 and 1388 of Part VI of *Mysore Gazette*, dated 22nd November 1928. The last date for receiving tender is 17th December 1928, till 2 P.M. Earnest money Rs. 140.

B. KRISHNA RAO,
Executive Engineer.

MYSORE RAILWAYS.

MYSORE DIVISION (OPEN LINES).

Dated 28th November 1928.

Notice is hereby given that separate sealed tenders will be received at the Office of the Executive Engineer, Open Line Division, Railways, Mysore, any working day up to 2 P.M., on the 15th December 1928, from contractors who are willing to undertake the execution of the following groups of works at Mysore South Station near Central Workshops area, Mysore.

1st Group—Construction of Station Building and Platform Latrine.

2nd Group—Construction of Station Master's Quarters (one unit) and Menials Quarters (3 units).

3rd Group—Earthwork cutting inclusive of all soils and forming bank wherever necessary with spoil inclusive of all lead and lift.

2. Every tender should be accompanied by an earnest money of Rs. 100 which can be paid either in currency note to the Executive Engineer, Mysore Railways, Mysore, along with the tender or can be paid to the Auditor, Mysore Railways, Mysore, and the receipt thereof enclosed along with the tender. Such of the tenderers who pay the amount to the Auditor should advise him that the amount is paid on account of a tender for the particular group of works tendered for.

(a) Tenders should be submitted in special form separately for each group of works. The forms can be obtained from the Executive Engineer, Mysore Railways, Mysore, on payment of Re. 1.

3. The earnest money of the unsuccessful tenderers will be returned as soon as possible after the tenders are disposed of.

4. Tenders which are not accompanied with the earnest money specified in para 2, will not be considered.

5. The successful tenderer should execute within a week from the date of notification of acceptance of his tender, the usual Railway Schedule Agreement. Failure to comply with this condition will render the tenderer liable for forfeiture of the earnest money.

6. The name of the accepted tenderer will be posted on the Notice Board of the Executive Engineer's Office. No enquiries regarding the acceptance or rejection of a tender will be replied.

7. The final acceptance of the tender will rest with the Agent, Mysore Railways, Mysore, who does not bind himself to accept the lowest or any tender and who further reserves to himself the right to reject, without assigning any reasons therefor, any or all the tenders.

8. Works should be started within a week from the date of acceptance of tenders, and a uniform monthly rate of progress should be guaranteed. The works agreed on should be completed in six months from date of starting. The Schedule gives the approximate quantity of works and these quantities are not guaranteed.

9. The time limit specified in para 8 should be strictly adhered to and any violation of this will render the contractor liable to forfeit his 5 per cent deposit amount under Clause No. 10 of the Schedule Agreement, not as a penalty but as ascertained and liquidated damages recoverable accordingly.

10. Plans and specifications and other details of works to be done are available for inspection, in the Executive Engineer's Office, Mysore Railways, Mysore, where intending tenderers may call and obtain required information during office hours.

11. In all matters of dispute regarding rates, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Engineering-in-Chief will be final and legally binding.

Schedule.

	Description of work	Unit	Quantity
	Station Building.		
1.	Earthwork excavation including filling in basement with spoil ..	1,000 c.ft.	1,228
2.	Concrete, broken stone in mortar	100 c.ft.	819
3.	Burnt stone in mortar in foundation and basement	„	430
4.	Burnt brick in mortar	„	2,785
5.	Arch work burnt brick in mortar including centering charges ..	„	152
6.	Burnt stone slabs 6″ thick dressed	S.ft.	228
7.	Teakwood truss for 16 feet clear span including hoisting and fixing and wood-oiling, all charges, as per approved design.	No.	1
8.	Brackets for verandah as per type design	„	5
9.	Teakwood wrought and put up including wood-oiling... ...	C.ft.	84·89
10.	Roofing with 1st class Mangalore Tiles over 2″ x 1″ teak reepers including chunam borders, etc., complete with R. M. C., rates for the tiles.	Sqr.	17·00
11.	Mangalore 1st class ridge tiles set in mortar	R.ft.	40
12.	Teakwood ornamental eave board 9″ x 1″ including painting ..	„	163
13.	Chunam plastering	Sqr.	41·24
14.	White and colour washing	„	41·24
15.	Teakwood panelled doors with hinges, hasps and staples, tower bolts, etc., complete as per approved design.	S.ft.	66½

No.	Description of work	Unit	Quantity
16	Teakwood windows with glazed inside, panelled outside shutters and iron bars with hinges, hooks, rings, etc., complete as per approved design.	S.ft.	35½
17	Teakwood glazed ventilators with iron bars, etc., complete as approved design.	„	12
18	Teakwood Ticket window as per type design ..	„	16½
19	Teakwood record racks 1″ thick planks including scantlings and fixing charges as per approved design.	„	17
20	Teakwood barrier as per type plan including fixing charges ...	„	41
21	C. I. Railing 7′ x 4′-6″ fixing charges only	No.	1
22	W. I. Gate including hinges, locking arrangements, etc, fixing charges only.	„	1
23	Flooring with 1½″ to 2″ Cuddapah slabs over 3 inches concrete bed including cement pointing, etc., complete with R. M. C. rates for slabs.	Sqr.	10·65
24	Chocolate painting	„	3·48
25	Teakwood finials	No	2
26	Teakwood pendants	„	6
	Platform Latrine.		
1	Earthwork excavation	1,000C.ft.	391
2	Concrete broken stone in mortar	100 C.ft.	196
3	Size stone in mortar	„	781
4	Size stone in prepared clay	„	300
5	Coping with stone in mortar and cement plastering ½″ thick..	R.ft.	107
6	Burnt stone slabs 6″ dressed	S.ft.	18
7	Burnt stone seats 18″ x 9″ x 12″ neatly dressed	No.	8
8	Cement pointing	Sqr.	12·51
9	Tarring two coats	„	9·45
10	Flooring with ¾″ cement plastering over 6″ concrete bed ...	„	183
11	Latrine pans, G. I.	No.	4
12	G. I. bucket	„	1
	Earth work.		
1	Earthwork cutting inclusive of all soils and forming bank wherever necessary with spoil inclusive of all lead and lift.	1,000C.ft.	2,00,000
	Menials quarters—(3 *units*).		
1	Earthwork excavation	1,000C.ft.	495
2	Burnt stone in mortar	100 C.ft.	534
3	Burnt brick in mud superstructure	„	898
4	Burnt brick in mortar	„	187
5	Burnt stone slabs 6″ thick roughly dressed	S.ft.	72
6	Plastering with mortar	Sqr.	20·20
7	Colour and white washing	„	20·20
8	Teakwood doors, battened (as per approved design) ...	S.ft.	27
9	Do windows with battened shutters and iron bars, etc., (as per approved design).	„	27
10	Teakwood work wrought and put up including wood oiling ...	C.ft	2,700
11	Roofing with First Class Mangalore tiles on 2″ x 1″ teak reepers including chunam borders with R. M. C. rates for tiles.	Sqr.	5·58
12	Ridge tiles set in mortar	R.ft.	22
13	Ventilating tiles	No.	6
14	Teakwood eave board 8″ x ¾″	R.ft.	120
15	Painting with Silicate chocolate	Sqr.	3·78
16	Teakwood finials, large	No.	3
17	Do small	„	6
18	Constructing oven	Lump sum	
19	Do cistern	„	...

No.	Description of work	Unit	Quantity
20	Supplying and fixing pestle and mortar	Lump sum	
21	Constructing drain	,,	...
22	Supplying and fixing teakwood hat rack and brackets ...	,,	...
23	Flooring with 6″ thick gravel including watering and tamping...	,,	...
	Station Master's Quarters—(1 *unit*).		
1	Earthwork excavation	1,000C.ft.	877
2	Concrete in sand mortar	100 C.ft.	310
3	Burnt stone in mortar	,,	784
4	Burnt brick in mud	,,	1,327
5	Do mortar	,,	281
6	Burnt stone slabs 6″ thick roughly dressed	S.ft.	128
7	Plastering with mortar	Square	31·21
8	Colour and white washing	,,	31·21
9	Pointing with mortar	,,	1·63
10	Flooring with 1½″ Cuddapah slabs over 3″ concrete bed including cement pointing with R. M. C. charges for slabs.	,,	3·88
11	Flooring with 6″ concrete in mortar and plastered with ½″ thick cement.	,,	0·18
12	Teakwood doors with battened shutters as per approved design.	S.ft.	117
13	Teakwood windows with battened shutters and iron bars, etc., complete as per approved design.	,,	60
14	Teakwood wrought and put up including wood oiling ...	C.ft.	25·6
15	Roofing with First Class Mangalore tiles on 2″ teak reepers including chunam borders with R. M. C. charges for tiles.	Square	7·54
16	Ridge tiles set in mortar	R.ft.	26
17	Painting with Silicate chocolate	Square	4·29
18	Constructing cement drain	R.ft.	30
19	Burnt brick in mortar cornice	,,	48
20	Constructing oven and sink	Lump sum	
21	Forming seats in the latrine	,,	...
22	Supplying pestle and mortar	,,	...
23	Clearing and levelling site	,,	...
24	Teakwood trellis work including fixing	S.ft.	37

M. RAMAIYA,
Executive Engineer.

MEDICAL DEPARTMENT.

DISTRICT HOSPITAL, KOLAR.

Dated 29th November 1928.

Sealed tenders in triplicate, on half sheet foolscap size paper will be received at the Office of the District Medical Officer, Kolar, by the undersigned on 5th January 1929 at 11 A.M., for the supply of articles of Bedding and Clothing, required for the use of the District Hospital, Kolar, for the year 1928-29.

For details, please refer to Part VI, page 1413 of the *Mysore Gazette*, dated 29th November 1928.

C. NARAYANA RAO,
District Medical Officer.

MISCELLANEOUS DEPARTMENTS.

OFFICE OF THE DIRECTOR OF AGRICULTURE IN MYSORE, BANGALORE.

Notice.

The attention of the public is drawn to notification dated 9th November 1928, calling for tenders for the supply of furniture to the Agricultural Department published in the *Mysore Gazette*, dated 22nd November 1928, on page 1386 of Part VI.

H. V. KRISHNAYYA,
For *Director of Agriculture.*